


THE LIMECRETE COMPANY LTD

CROSS SECTION



LIME/SAND SCREED 75MM

FOR FINAL FLOOR FINISH INCLUDE CHOICE OF AGGREGATE, GRIND AND POLISH ↑



UNDERFLOOR HEATING INSTALLED ON SLAB BY HEATING CONTRACTOR ↑



LIMECRETE SLAB 100MM – 150MM ↑




GEOTEXTILE ↑



RECYCLED FOAMED GLASS INSULATION 100MM – 170MM ↑



GEOTEXTILE ↑



LEVELLED AND COMPACTED GROUND PREPARED BY YOURSELVES ↑

APPROXIMATE SCHEDULE

- WEEK 1 – NO FOOT TRAFFIC ON SLAB
- WEEK 2 – LIGHT FOOT TRAFFIC WITH COVER PROTECTION
- WEEK 3 – UNDERFLOOR HEATING INSTALLED
- WEEK 4 – SCREED PLACED
- WEEK 5 – NO FOOT TRAFFIC ON SCREED
- WEEK 6 – LIGHT FOOT TRAFFIC
- WEEK 7 – WORK AS NORMAL

TIMING WILL VARY DEPENDING ON VARIOUS FACTORS SUCH AS TEMPERATURE, INCLUDING AMBIENT TEMPERATURE OF BUILDING WHEN BEING PLACED.

REGISTERED IN ENGLAND No. 6210907
GREY GABLES, CLAXTON CHURCH ROAD, ASHBY ST MARY, NORFOLK, NR14 7BZ
PHONE 01953 888011 FAX 0844 888 5850 MOBILE 07900 828895

LOU@LIMECRETE.CO.UK

PRINTED ON RECYCLED PAPER